

**GOVERNMENT OF ORISSA**



**PANCHAYATI RAJ DEPARTMENT**

**BID DOCUMENT**

**NAME OF THE WORK: - DETAILED ESTIMATE FOR CONSTRUCTION OF  
DAY CARE SUB CENTER RANAGUNDI, RANAGUNDI , G.P-  
RANAGUNDI**

**Bid Identification/DTCN No. 43651 29-12-21 / P.S Danagadi**

**PANCHAYAT SAMITI, DANAGADI.**

**SCHEDULE-A (CERTIFICATE OF NO RELATIONSHIP)**

I/We hereby certify that I/We\* am/are\* related not related (\*) to any officer of PR Deptt. of the rank of Assistant Engineer & above and any officer of the rank of Assistant / Under Secretary and above of the P.R Deptt, Govt. Of Odisha. I/We\* am/are\* aware that, if the facts subsequently proved to be false, my/our contract will be rescinded with forfeiture of E.M.D and security deposit and I/We\* shall be liable to make good the loss or damage resulting from such cancellation. I/We also note that, non-submission of this certificate will render my / our tender liable for rejection.

(\*)Strike out which is not applicable.

**SCHEDULE-B CERTIFICATE OF EMPLOYMENT OF UNEMPLOYED GRADUATE ENGINEER/DIPLOMA HOLDERS (For special class / "A" class contractors only)**

I / We hereby certify that at present the following Engineering personnel are working with me / in our firm / company and their bio-data are furnished below.

Sl. No.	Name of the Engineering personnel appointed for supervising contractor's work with address	Qualification	Date of Appointment	Monthly emolument	Whether full time engagement and continuous	If they are superannuated / retired / dismissed or removed personnel from state Govt. / Central Govt. / Public Sector undertaking / Private Companies and or any one ineligible for Government service.
1	2	3	4	5	6	7

**SCHEDULE- C FORMAT OF AFFIDAVIT**


- The undersigned do hereby certify that all the statements made in the required attachments are true and correct.
- The undersigned also hereby certifies that neither our firm M/s \_\_\_\_\_ nor any of its constituent partners have abandoned any road/ bridge/Irrigation /Buildings or other project work in India nor any contract awarded to us for such works have been rescinded during the last five years prior to the date of this bid.
- The undersigned hereby authorized and request (s) any bank, person, firm or Corporation to furnish pertinent information as deemed necessary and as requested by the Department to verify this statement or regarding my (our) competency and general reputation.
- The undersigned understands and agrees that further qualifying information may be requested and agree to furnish any such information at the request of the Department.

(Signed by an Authorized Officer of the firm)

Title of Officer :

Name of Firm :

Date: :

 Block Development Officer, Danagadi	 Asst. Ex. Engineer Danagadi Block.	APPROVED FOR (-----) pages only  Addl. Project Director (Tech.), DRDA, Jajpur
---	--	--

Sold for the work " Construction of Day care sub center Ranagundi", **Ranagundi** ,Danagadi Block" on payment of Rs. -----/- (Rupees -----) only vide Money Receipt No ..... Dt ..... against BC / Bank Draft No..... Dt..... payable at SBI Duburi Project, Danagadi.

Block Development Officer,  
Danagadi.




## BILL OF QUANTITIES

Name of the Work:  
CONSTRUCTION OF DAY CARE SUB CENTRE , RANAGUNDI

Sl No.	Description of item of work	Quantity	Unit	Rate in Rs.	Amount In Rs
<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>
1	Earth work in excavation of foundation in trenches in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing & leveling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering, if necessary from foundation complete as directed by Engineer-in-charge	72.52	One Cubic meter	184.55	13384.00
2	Filling in Foundation and Plinth and floor with sand, watered and rammed including all cost of sand, conveyance, royalty with labour and T & P required for the work.as per direction of Engineer-in-charge.	67.48	One Cubic meter	535.27	36120.00
3	Cement Concrete of proportion (1:3:6) using 4cm and downgraded size Hard Granite Crusher Broken metal for foundation, flooring concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance, royalty of materials with all labour charges as directed by Engineer-in-Charge.	19.48	One Cubic meter	4628.12	90156.00
4	R.C.C. work of M-20 grade with 20mm and down grade black hard granite (crusherbroken) stone chips including hoisting and laying, cost, conveyance and royalty of materials, curing etc complete as per direction of Engineer-in-charge	42.06	One Cubic meter	4854.60	204184.00
5	Rigid and smooth centering & shuttering at all heights of all types of work using required scaffolding, T & P, centering shuttering including all taxes of materials cost of scaffolding conveyance and dismantling and disposing debris clear of work site complete as per the direction of the Engineer-in-charge.				
(a)	For column base & plinth band	43.64	One square meter	100.92	4404.00
(b)	For columns, wall beam and cross beam	87.08	One square meter	726.31	63247.00
(c)	For Lintel band	26.18	One square meter	261.24	6839.00
(d)	For roof slab, verandah, door and window chajja,	138.16	One square meter	425.16	58740.00
6	Supplying, fitting, placing uncoated HYSD bar reinforcement for RCC work including cost, conveyance and taxes of MS rods or HYSD steel and binding wires of 18-20 gauge and labour charges requires for the work etc. complete in all floors.	42.06	One qntl.	7494.14	315204.00
7	Fly ash brick in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75 kg/cm <sup>2</sup> with dimension tolerance +/- 8% incl. splays cutting circular moulding, chamfering and corbelling etc. incl. cost of all materials labour T&P, cess, etc. as per direction of Eng.in.charge.	21.96	One Cubic meter	4285.74	94115.00
8	Fly ash brick in cement mortar (1:6) in super structure having crushing strength not less than 75 kg/cm <sup>2</sup> with dimension tolerance +/- 8% incl. splays cutting circular moulding, chamfering and corbelling etc. incl. cost of all materials labour T&P, cess, etc. as per direction of Eng.in.charge.	40.58	One Cubic meter	4319.07	175268.00

9	16 MM (5/8") thick cement plaster in C.M.(1:6) finishing smooth to inside rough surface of 5" / 10" thick brick walls after racking out the joints including watering and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour charges required for the work etc..complete including cess.	396.83	One square meter	198.32	78699.00
10	12 mm (1/2") thick cement plaster in C.M.(1:6) finishing smooth to outside smooth surface of brick walls after racking out the joints including watering and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour charges required for the work etc. complete.	460.43	One square meter	139.45	64207.00
11	Supplying fitting fixing of MS doors & windows incl. cost, conveyance, taxes, T & P of all materials etc complete including cess as per direction of Engineer-in Charge	1770.84	One kg.	80.00	141667.00
12	Supplying, fixing verified tiles (600mmx600mm) in floors on 25mm thick bed of cement mortar(1:1) jointed with neat cement slurry.	97.50	One square meter	1104.28	107667.00
13	Supplying, fixing verified tiles (600mmx600mm) in walls, dado, skirting on 12mm thick cement plaster(1:3) jointed with neat cement slurry.	149.55	One square meter	1223.76	183013.00
14	Supplying, fixing ceramic floor tiles (300mmx300mm) in floors, treads of steps, landings on 25mm thick bed of cement mortar(1:1) jointed with neat cement slurry.	6.08	One square meter	970.11	5898.00
15	Supplying, fixing RCC jally in skylights (0.45m x 0.30m)	02	Nos	100.00	200.00
16	Supplying and painting 2 coats with synthetic enamel paint over one coat of primer on MS doors & windows, including cost of paint, labour, T&P, etc. complete. including cess.	45.75	One square meter	187.33	8570.00
17	Cement priming one coat to walls of approved quality.	980.83	One square meter	83.12	81527.00
18	Supplying, finishing walls with water proofing weather coat paint two coats of approved shade outside the building, T&P, labour, etc. all complete.	473.53	One square meter	70.53	33398.00
19	Wall painting two coats with plastic emulsion paint	494.33	One square meter	56.80	28078.00
20	Providing, supplying and painting of sign board and display board of size 1.20m x 1.20m x 0.25m(thick) above G.L. and 0.45m below G.L. and shall be plastered, painted and writing etc. as per direction of Eng. In.charge..	1	One No.	5000.00	5000.00
<b>Total</b>					<b>1799585.00</b>

**Total 20 ( Twenty ) items Only (Rupees Seventeen Lakh Ninty Nine Thousand Five Hundred Eighty Five) only.**

**Asst. Executive Engineer, Danagadi**      **BDO, Danagadi**      **Addl. Project Director (Tech.), DRDA, Jajpur**

My / our quoted rate is \_\_\_\_\_ % (both in figures and words) excess over / less than / equal to the above estimated cost.

**Signature of Tenderer**